

Dennington Parish Council		RISK ASSESSMENT			PC 01 - 06 (April 2022)	
ACTIVITY COVERED BY THIS ASSESSMENT: <b>Roadworks. Dennington to erect &amp; Maintain a notice Board on verge adjacent to the highway.</b>						
SIGNIFICANT HAZARDS				ASSESSMENT OF RISK		
		INSIGNIFICANT	LOW	MED	HIGH	
1.	Operatives struck by moving vehicles				X	
2.	Operatives struck by surface plant				X	
3.	Traffic control risk to public			X		
4.	Traffic struck by surface plant			X		
5.	Noise emissions from vehicles		X			
6.	Surface plant contact with existing services				X	
7.	Surface plant contact with overhead lines				X	
8.	Health hazards from work			X		
9.	Injury to pedestrians				X	
10.						
ACTIONS ALREADY TAKEN TO REDUCE THE RISKS:						
Relevant Regulations:						
Highways Act 1980, New roads & Street works Ac 1991 Traffic Signs manual – Chapter 8 DOT ACoP Safety at Street Works & road works HSG 151 Protecting the Public, your next Move.						
PLANNING: (e.g. pre-contract, maintenance, work sequence, interaction between trades or contractors)						
Traffic control where necessary will be planned in liaison with local authority and police. First aid welfare & emergency requirements will be assessed at this stage. Plans will be obtained to locate any existing hazards from services. Safe pedestrian routes will be planned. COSHH manual handling, PPE & noise assesemnts will be reviweed, brought to site and the information passed to operatives.						
PHYSICAL: (e.g. access, ppe, requirements, equipment requirements, barriers/fencing, signs)						
PPE will be provided as indicated by local assessment – clothing including high visibility wear, hearing, eyes, foot & head protection. All personnel on site including visitors will wear high visibility clothing. Traffic control signs lighting and safety zones will be set out in accordance with the Approved Code of Practice. A vehicle on site will be fitted with an amber-flashing beacon. Minimum widths for moving traffic will be maintained. Additional signs & warning lights for use in adverse weather conditions will be available on site.						
MANAGERIAL/SUPERVISORY: (e.g. checks and actions required by supervision)						
The Parish Council will monitor the work in progres. Any changes to planned arrangements are to be authorised in writing. Traffic and pedestrian controls will be checked at the end of each work period and working day.						
TRAINING: (e.g. specific employee /operator training or certification required)						
Plant operator training & certification to CITB standards is required supervisors to be trained in traffic management: they & operatives to be qualified to Street Works (qualification of supervisors & operatives) Regulations 1992.						
<i>This generic assessment must be completed by addition of specific site details on the reverse</i>						